Site Address: 10 SIX RIVERS CR S Parcel No: 031-0260-032	Sub-Type: RES Housing (Y/N): N	
CONTRACTOR ZIMMERMAN ROOFING 3569 RAMONA AV SAURAMENTO CA 95826	OWNER KING RAYMOND D/ROSA 10 SIX RIVERS CR SACRAMENTO CA 95831	<u>ARCHITECT</u>
Nature of Work: TEAR OFF/REROOF	WITH MONIER TILE/33 SQ	
CONSTRUCTION LENDING AGENCY: of the work for which this permit is issued (Sec. 30)	I hereby affirm under penalty of perjury that 97, Civ. C).	there is a construction lending agency for the performance
	TION: I hereby affirm under penalty of	perjury that I am licensed under provisions of Chapter 9
Deer se Class C32 License Number 557		
totlowing reason (Sec. 7031.5, Business and Profes any structure, prior to its issuance, also requires the of the Contractors License Law (Chapter 9 (comm	ssions Code; any city or county which requir applicant for such permit to file a signed standard with Section 7000) of Division 8 of applion. Any violation of Section 7031.5 by	t I am exempt from the contractors License Law for the es a permit to construct, alter, improve, demolish, or repair tement that he or she is licensed pursuant to the provisions f the Business and Professions Code) or that he or she is any applicant for a permit subjects the applicant to a civil
for sale (Sec. 7044, Business and Professional Co thereon, and who does such work himself or hersel	de: The Contractors License Law does no If or through his/her own employees, provid	ill do the work, and the structure is not intended or offered of apply to an owner of property who builds or improves ed that such improvements are not intended or offered for her-builder will have the burden of proving that he/she did
Code The Contractors License Law does not appl contractors) licensed pursuant to the Contractors Licensed pursuant to the	y to an owner of property who builds or imp	onstruct the project (Sec. 7044, Business and Professions proves thereon, and who contracts for such projects with a
I am exempt under Sec.	B & PC for this reason:	
Date	Owner Signature	
all measurements and locations shown on the applied	cation or accompanying drawings and that the ibited locations for such improvements. This	representation of the applicant, that the applicant verified he improvement to be constructed does not violate any law s building permit does not authorize any illegal location of
relating to building construction and herby authorize	e representative(s) of this city to enter upon t	comply with all city and county ordinances and state laws he abovementioned property for inspection purposes.
Date 10-14-99	Applicant/Agent Signature <b>Lelly</b>	cory
WORKER'S COMPENSATION DECLARA	ATION: I hereby affirm under penalty of pent to self-insure for workers' compensation	11
which this permit is issued. My workers' compensation	ation insurance, as required by Section 3700 tion insurance carrier and policy number are:	of the Labor Code, for the performance of the work for
Carrier STATE COMP INS FUND	Policy Number 713-98-2	021 Exp Date 10/01/2000
shall not employ any person in any manner so as t subject to the workers' compensation provisions of S	to become subject to the workers' compensa Section 3700 of the Labor Code, I shall forth	e performance of the work for which this permit is issued,I ation laws of California and agree that if I should become with comply with those provisions.
Date 10-14-99	Applicant Signature July	coy
WARNING FAILURE TO SECURE WORKER' CRIMINAL PENALTIES AND CIVIL FINES UP COMPENSATION, DAMAGES AS PROVIDED FOR	P TO ONE HUNDRED THOUSAND DO	A VOUL AND SHALL SUBJECT AN EMPLOYER TO LLARS (\$100,000) IN ADDITION TO THE COST OF DDE, INTEREST AND ATTORNEY'S FEE.

**CITY OF SACRAMENTO** 

1231 I Street, Sacramento, CA 95814

Permit No: 9911653

Insp Area:



DEPARTMENT	Of
PLANNING AND	DEVELORMENT

# CITY OF SACRAMENTO CALLEORNIA

1231 I STREET ROOM 200 SACRAMENTO, CA 95814-2998

Pennik Services 916-264-7619 5 NX 916-264-7046

SIX RUER TILE ROOF WORKSHEET

This worksheet must be filled out whenever any type of tile roof is applied for,

If the answer to question #5 is yes, a written engineering report from a registered engineer must be provided with each application.

1.	BRAND AND MODEL OF TILE MONION VILLA
2.	TILE WEIGHT PER SQUARE 600
3.	WEIGHT OF ROOF SYSTEM PER SQUARE 150
4	TOTAL WEIGHT OF ROOF SYSTEM
<b>5</b> .	DOES TOTAL WEIGHT OF ROOF SYSTEM EXCEED 750# PER SQUARE? YES NO
<b>6</b> .	ROOF SLOPE 4/7

PLEASE A PROVIDE A SEPARATE WORKSHEET FOR EACH APPLICATION INVOLVING A TILE ROOF.

Del attached engin, separa

Paul Zacher - Structural Engineers 4701 Lakeside Way Fair Oaks, CA 95628

TEL: 916.961.3960 FAX: 916.961.3960

September 25, 1999

Zimmerman Roofing 3560 Ramona Avenue Sacramento, CA 95826 TEL: 916.454.3667 FAX: 916.455.3784 TEL (Jeff): 916.392.1971 FAX (Jeff): 916.392.6853 FAX (Framer): 916.383.5308



Attn. Mr. Jeff Tucker,

re: Job 99250: KING

Subject: Structural Investigation Report of the Roof for the Residence located at 10 Six River, Sacramento, CA 95831

As requested by Mr. Jeff Tucker, this is a report to determine what needs should be addressed to correct any structural deficiencies of the roof. Paul Zacher visited the site September 24, 1999. The investigation was made to determine the existing condition of the structure. All information, data and analysis contained within this report is based on the 1997 Uniform Building Code.

The following is based on visual observations with no subsurface investigation being made.

#### **DESCRIPTION**:

Residence. Type of Facility:

Estimated 1970's vintage. Year Built:

Residential.

Occupancy:

One. No. of Stories:

Approximately 2000 square feet with a first story plate height of 8 feet. **Dimensions**:

#### CONSTRUCTION:

Roof:

The roof covering will consist of a Light Weight Concrete Tile over 1/2" solid sheathing. The living and garage areas are framed with pre-engineered wood trusses spaced at 24" on center.

#### CONCLUSIONS:

Roof:

The living and garage areas have sufficient structural capacity for the applied live and dead loads.

Periened by Mott P. 10/12/99 1/9 Mox. 600 #/sq. material For this engineering

king



Paul Zacher – Structural Engineers 4701 Lakeside Way Fair Oaks, CA 95628

**RECOMMENDATIONS:** 

None

It shall be noted that small hairline cracking may occur at exterior stucco and interior gypboard finished walls which are load bearing or distributing roof strut loads. These cracks are a natural occurrence as the existing structure re-distributes the new roof weight. They are cosmetic in nature and are not an indication of a structural hazard or failure.

It shall be noted that some deflection of the rafters may be evident after installation of the tile. The existing roof framing has deflected but this may not be readily evident due to the uneven nature of the existing roofing material. Concrete tile is a very consistent and uniform product and when installed in an even plane, even small deflections can become apparent. This is only a cosmetic issue and not a structural concern.

The inspection consisted of visual observation only, made solely to determine the structural capacity of the existing roof. Analysis does not determine any effects on the overall structure under lateral forces or effects on the foundation unless specifically noted in the calculations and in this document. No warranties, expressed or implied, are made or intended in conjunction with this report. The inspection was made only to the portions that were accessible. The specific items noted were those that were observable and there may be defects which are not observable, or are hidden by architectural and structural materials.

If you have any questions on the above, do not hesitate to call.

Sincerely,

Paul Zacher, P.E., S.E.

file

### **DESIGN LOADING:**

Roof Pitch	4	in 12
Pitch Adjustment Factor	1.05	

### LOCATION: ROOF

MATERIAL	<b>WEIGHT</b>	
Light Weight Tile	6.00	psf
Roofing felt	0.30	psf
1x4 skip sht'g	1.09	psf
1/2" OSB/ plywood	1.50	psf
2x6 rafters @ 24" oc	1.00	psf
Load	9.9	psf
Roof Pitch Adjustment	0.54	psf
Total Load	10.4	psf

## LOCATION: TOP CHORD

MATERIAL	<b>WEIGHT</b>	
Light Weight Tile	6.00	psf
Roofing felt	0.30	psf
1/2" OSB/ plywood	1.50	psf
1x4 skip sht'g	1.09	psf
2x4 truss @ 24" oc	<u>1.28</u>	psf
Load	10.2	psf
Roof Pitch Adjustment	0.55	psf
Total Load		psf

## LOCATION: BOTTOM CHORD

MATERIAL	WEIGHT		
Batt/blown insul		0.50	psf
2x4 truss @ 24" oc		0.64	psf
1/2" Gypboard		<u>2.50</u>	psf
J 1	Load	3.6	psf

Paul Zacher-Structural Engineer

4701 Lakeside Way Fair Oaks, CA 95628 TEL: (916) 961-3960 FAX: (916) 961-3960 Title : Dsgnr: Description : Job # Date: 9:19AM, 25 SEP 99

Scope:


Rac 510304 User KW-0602844, Ver 5 1.3 22-Jun-1999, Win32 (c) 1883-99 ENERCALC

**Timber Beam & Joist** 

c:\enercalc\test.ecw:Calculations

**Description** RAFTERS AND BEAMS

	forma			William School Street,	
		rafter	porch	garage	
Firmber Section		2x6	4x12	4x12	
Beam Width	in	1.500	3.500	3.500	
Beam Depth	in	5.500	11.250	11.250	
e: Unbraced Length	ft	2.00	4.00	0.00	
Timber Grade	ŀ	Douglas Fir - Larch,	Douglas Fir - Larch, D	Douglas Fir - Larch,	
b - Basic Allow	psi	875.0	1,000.0	875.0	
v - Basic Allow	psi	95.0	95.0	95.0	
Elastic Modulus	ksi	1,600.0	1,700.0	1,600.0	
Load Duration Factor	1	1.250	1.250	1.250	
Member Type	1	Sawn	Sawn	Sawn	
Repetitive Status		Repetitive	No	No	
enter Span Data					
Span	ft	12.00	16.50	16.00	
Dead Load	#/ft	19.80	62.00	62.00	
ive Load	#/ft	32,00	96.00	96.00	
	Ratio =	0.9221	0.6419	0.6831	
esults	raio -		Marie College College		
Vimax @ Center	in-k	11.19	64.52	60.67	
@ X =	ft	6.00	8.25	8.00	
fb . Actual	psi	1,479.5	874.0	821.8	
Fb : Allowable	psi	1,604.5	1,361.4	1,203.1	
D. ANDIVADIC	po.	Bending OK	Bending OK	Bending OK	
£ 6.1		52.4	44.1	42.8	
fv : Actual	psi	118.8	118.8	118.8	
Fv · Allowable	psi	Shear OK	Shear OK	Shear OK	
eactions					
@ Left End DL	lbs	118.80	511.50	496.00	
LL	lbs	192.00	792.00	768.00	
Max. DL+LL	lbs	310.80	1,303.50	1,264.00	
@ Right End DL	lbs	118.80	511.50	496.00	
LL LL	lbs	192.00	792.00	768.00	
Max. DL+LL	lbs	310.80	1,303.50	1,264.00	
eflections					
Center DL Defl	iΠ	-0.278	-0.146	-0.138	
L/Defl Ratio		518.7	1,351.9	1,395.5	
Center LL Defi	in		-0.227	-0.213	
L/Defl Ratio		320.9	873.1	901.2	
Center Total Defl	in		-0.373	-0.351	
Location	fi	1	8.250	8.000	
COOKIO!		198.3	530.5	547.6	



# VisualAnalysis 3.50.c Report

09/25/99 09:13:06

Project:

File: C:\WINDOWS\Desktop\King.vap Company: PK Associates Engineers

Engineer: Paul Zacher Default Units: Feet, Pounds, Degrees, °Fahrenheit, Seconds.

#### Nodes

Node	X ft	Y ft	Fix	DΧ	Fix	DY	Fix	RZ
N1	0.00	0.00	Yes		Yes		No	
N2	10.00	0.00	No		No		"	
N3	19.00	0.00	"		Yes		"	
N4	08.00	0.00	11		No		"	
N5	38.00	0.00	"		Yes		"	
N6	7.00	2.33	"		No		"	
N7	31.00	2.33	"		"		"	
N8	13.00	4.33	"		"		"	
N9	25.00	4.33	"		"		"	
N10	19.00	6.33	"		"		"	

### Member Elements

Member	Section	n Material	Length ft
M1	SS2x4	Wood	10.00
M2	"	"	9.00
M3	rr	"	9.00
M4	"	"	10.00
M5	**	"	7.38
M6	"	"	6.32
M7	er	"	6.32
M8	"	"	6.32
M9	**	"	6.32
M10	**	"	7.38
M11	71	"	3.80
M12	"	"	5.27
M13	11	**	7.40
M14	**	"	6.33
M15	"	"	7.40
M16		"	5.27
M17	"	"	3.80

## Section Properties

Category	Section			Sy+ in^3	
Wood Sha	SS2x4	5.25	5.36	3.06	3.06

## Material Properties

Material	Strength psi	Elasticity psi		Density 1b/ft^3
Wood	-NA-	1700000.00	0.36	40.47

## Load Combination Summary

Equation Case: Equation Case 1
Combination: +1D+1L+1Lr
Contributing Cases & Source
Service Case 1 (Dead loads)
Service Case 2 (Roof Live loads)

## Member Uniform Loads

Load Case	Member	Direction	Offset E	End Offset ft	Magnitude
Service Case 1	M1	DY proj.	0.00	10.00	-7.20 lbs/ft
"	M2	" []	0.00	9.00	-7.20 lbs/ft
"	M3	"	0.00	9.00	-7.20 lbs/ft
"	M4	"	0.00	10.00	-7.20 lbs/ft
"	M5	"	0.00	7.38	-21.40 lbs/ft
"	M6	"	0.00	6.32	-21.40 lbs/ft
"	м7	"	0.00	6.32	-21.40 lbs/ft
"	M8	"	0.00	6.32	-21.40 lbs/ft
"	M9	"	0.00	6.32	-21.40 lbs/ft
"	M10	"	0.00	7.38	-21.40 lbs/ft
Service Case 2	M5	"	0.00	7.38	-32.00 lbs/ft
and a service case a	M6	"	0.00	6.32	-32.00 lbs/ft
77	M7	rr	0.00	6.32	-32.00 lbs/ft
<i>''</i>	M8	"	0.00	6.32	-32.00 lbs/ft
77	M9	"	0.00	6.32	-32.00 lbs/ft
$\overline{n}$	M10	"	0.00	7.38	-32.00 lbs/ft

## Nodal Reactions

Node	Load Case	FX 1bs	FY 1bs	MZ lb-ft
N I	Equation Case 1	0.00	325.98	-NA-
	Service Case 1	-AM-	-NA-	-NA-
"	Service Case 2	-NA-	-NA-	-NA-
N3	Equation Case 1	-NA-	1650.84	-NA-
11	Service Case 1	-NA-	-NA-	-NA-
"	Service Case 2	-NN-	-NA-	-AM-
N5	Equation Case 1	-NA	325.98	-NA-
"	Service Case 1	-NA-	-NA-	-AN-
"	Service Case 2	-NA-	-NA-	-NA-

## Member Extreme Results

Member	Axial(lc) lbs	Vy (lc) <i>lbs</i>	Mz(lc) lb-ft	Dx(lc) in	Dy (lc) in
 мі	426.21(3)	-51.09(	3) -86.47(3	3) -0.00(3	3) -0.17(3)
• •	426 21 ( 3)	20.91(3	) 94.76(3)	0.01(3)	-0.00(3)
MC.	-170 481 3	) -26.61(	3) -86.47(	3) 0.00(	3) -0.02( 3
"	-170 487 3	38.19(	3) 14,77(3)	0.01(3)	-0.00(3)
<b>M</b> 3	-170.48( 3	) -38.19(	3) -86.47(	3) 0.00(	3) -0.02(3
	-170.481.3	26.61(	3) 14.77(3)	0.00(3)	-0.00(3)
<b>M</b> 4	426,21(3)	-20.91(	3) -86.47(3	3) 0.00(3	3) -0.17(3)
"	426.21(3)	51.09(3	3) 94.76(3)	0.01(3)	-0.00(3)
M5	-500.75( 3	) -199.82	( 3) -230.32	2(3)-0.00	)(3) <b>-0.18(</b>
"	-382.69( 3	) 154.85(	3) 184.73(	3) -0.00(	3) -0.00( 3
M6	-138.13(3	) -137.77	(3) -230.3	2 (3) -0.03	1 (3) -0.04 (
"	-36.81(3)	166.18(	3) 56.99(3	) -0.00( 3)	0.02(3)

```
706.60(3) -157.15(3) -173.20(3) -0.01(3) -0.05(3)
M7
          807.92(3) 146.81(3) 83.46(3) 0.00(3) -0.01(3)
 **
          706.60(3) -146.81(3) -173.20(3) 0.01(3) -0.05(3) 807.92(3) 157.15(3) 83.46(3) 0.01(3) -0.01(3)
М8
           -138.13(3) -166.18(3) -230.32(3) 0.01(3) -0.03(3)
M9
          -36.81(3) 137.77(3) 56.99(3) 0.01(3) -0.01(3)
          -500.75(3) -154.85(3) -230.32(3) 0.01(3) -0.17(3)
M10
          -382.59(3) 199.82(3) 184.73(3) 0.01(3) 0.00(3)
 **
          -440.28(3) 0.00(3) 0.00(3) 0.02(3) -0.02(3)
M11
                        0.00(3) 0.00(3) 0.02(3) -0.02(3)
11
          -440.28(3)
                        0.00(3) 0.00(3) -0.02(3) -0.02(3)

0.00(3) 0.00(3) -0.01(3) -0.01(3)

0.00(3) 0.00(3) 0.00(3) -0.01(3)

0.00(3) 0.00(3) 0.01(3) 0.00(3)
Mis
          437.17(3)
          437.17(3)
M13
          -673.68(3)
          -673.68(3)
          -809.15(3) -0.00(3) -0.00(3) -0.01(3) -0.00(3)
M14
          -809.15(3) -0.00(3) 0.00(3) -0.00(3) -0.00(3)

-673.68(3) 0.00(3) 0.00(3) -0.00(3) -0.02(3)

-673.68(3) 0.00(3) 0.00(3) 0.00(3) -0.00(3)
 "
M15
 "
                        0.00(3) 0.00(3) 0.02(3) -0.01(3)
           437.17(3)
M16
          437.17(3) 0.00(3) 0.00(3) 0.02(3) -0.00(3)
M17
          -440.28(3) -0.00(3) -0.00(3) -0.02(3) -0.02(3)
           -440.28(3) -0.00(3) 0.00(3) -0.01(3) -0.02(3)
```

## BENDING & COMP: TRUSS 1; MEMBER 5

Design based on 1997 UBC 2321 Division V and ANSI/TPI 1-1995

Grading:

2x or 4x Doug-fir larch: No. 2

Assumptions.

Solid sheathing on top chord of truss. Therefore,

continuous lateral support is provided along compression face

Maximum center-center spacing = 24"

Width, b	1.5 inches			
Depth, d	3.5 inches			
Length	7.38 feet			
Max Axial Comp. C	500 lbs			
Max Reaction, R	199 <b>lb</b> s			
Max Moment, M	230 ft-lbs			
Max LL Deflection	0.07 inches			
Max TL Deflection	0.18 inches			
LL Defl Criteria = L/	240			
TL Defl Criteria = L/	180			
Duration factor. Cd	1.25			
Repetitive Factor, Cr	1.15			
Size Factor. Cf bending	1.5 1.5 for 2x4, 1.3 for 2x6			
Size Factor, Cf comp	1.15 1.15 for 2x4, 1.1 for 2x6			
Buckling Factor, CT =	1.22			
fc =	95 psi			
Fcc=	911 psi			
Fc*	1869 psi			
F'c=	794 psi			
fb=	901 psi			
F'b=Fb*=	1887 psi			
Shear D/C ratio	$0.48 \le 1.0$ , Member OK			
Interaction equation:				
(fc/F'c)^2 +				
fb/(F'b(1-fc/Fce)) =	$0.55 \le 1.0$ , Member OK			
Live Load defl ratio	$0.19 \le 1.0$ , Member OK			
Total Load defl ratio	$0.37 \le 1.0$ , Member OK			
1				