

CITY OF SACRAMENTO

1231 I Street, Sacramento, CA 95814

Permit No: 9904938

Insp Area: 2

Site Address: 327 ZEPHYR RANCH DR SAC

Parcel No: 031-0410-079

Sub-Type: RES

Housing (Y/N): N

CONTRACTOR

ZIMMERMAN ROOFING
3560 RAMONA AV
SACRAMENTO CA 95826

OWNER

FONG SHIRLEY N
327 ZEPHYR RANCH DR
SACRAMENTO CA 95831

ARCHITECT

Nature of Work: 22 SQ TEAR OFF AND REROOF WITH PIONEER TILE

CONSTRUCTION LENDING AGENCY : I hereby affirm under penalty of perjury that there is a construction lending agency for the performance of the work for which this permit is issued (Sec. 3097, Civ. C).

Lender's Name _____ Lender's Address _____

LICENSED CONTRACTORS DECLARATION: I hereby affirm under penalty of perjury that I am licensed under provisions of Chapter 9 (commencing with section 7000) of Division 3 of the Business and Professions Code and my license is in full force and effect.

X License Class C39 License Number 557559 Date 00/02 Contractor Signature Alma Dolia Gonzalez

OWNER-BUILDER DECLARATION: I hereby affirm under penalty of perjury that I am exempt from the contractors License Law for the following reason (Sec. 7031.5, Business and Professions Code; any city or county which requires a permit to construct, alter, improve, demolish, or repair any structure, prior to its issuance, also requires the applicant for such permit to file a signed statement that he or she is licensed pursuant to the provisions of the Contractors License Law (Chapter 9 (commencing with Section 7000) of Division 3 of the Business and Professions Code) or that he or she is exempt therefrom and the basis for the alleged exemption. Any violation of Section 7031.5 by any applicant for a permit subjects the applicant to a civil penalty of not more than five hundred dollars (\$500.00);

____ I, as a owner of the property, or my employees with wages as their sole compensation, will do the work, and the structure is not intended or offered for sale (Sec. 7044, Business and Professional Code: The Contractors License Law does not apply to an owner of property who builds or improves thereon, and who does such work himself or herself or through his/her own employees, provided that such improvements are not intended or offered for sale. If, however, the building or improvement is sold within one year of completion, the owner-builder will have the burden of proving that he/she did not build or improve for the purpose of sale.)

____ I, as owner of the property, am exclusively contracting with licensed contractors to construct the project (Sec. 7044, Business and Professions Code: The Contractors License Law does not apply to an owner of property who builds or improves thereon, and who contracts for such projects with a contractor(s) licensed pursuant to the Contractors License Law).

____ I am exempt under Sec. _____ B & PC for this reason: _____

Date _____ Owner Signature _____

IN ISSUING THIS BUILDING PERMIT, the applicant represents, and the city relies on the representation of the applicant, that the applicant verified all measurements and locations shown on the application or accompanying drawings and that the improvement to be constructed does not violate any law or private agreement relating to permissible or prohibited locations for such improvements. This building permit does not authorize any illegal location of any improvement or the violation of any private agreement relating to location of improvements.

I certify that I have read this application and state that all information is correct. I agree to comply with all city and county ordinances and state laws relating to building construction and hereby authorize representative(s) of this city to enter upon the abovementioned property for inspection purposes.

X Date 5-17-99 Applicant/Agent Signature Alma Dolia Gonzalez

WORKER'S COMPENSATION DECLARATION: I hereby affirm under penalty of perjury one of the following declarations:

____ I have and will maintain a certificate of consent to self-insure for workers' compensation as provided for by Section 3700 of the Labor Code, for the performance of work for which the permit is issued.

____ I have and will maintain workers' compensation insurance, as required by Section 3700 of the Labor Code, for the performance of the work for which this permit is issued. My workers' compensation insurance carrier and policy number are:

Carrier STATE COMP INS FUND Policy Number 713-98-2021 Exp Date 10/01/1999

____ (This section need not be completed if the permit is for \$100 or less) I certify that in the performance of the work for which this permit is issued, I shall not employ any person in any manner so as to become subject to the workers' compensation laws of California and agree that if I should become subject to the workers' compensation provisions of Section 3700 of the Labor Code, I shall forthwith comply with those provisions.

X Date 5-17-99 Applicant Signature Alma Dolia Gonzalez

WARNING: FAILURE TO SECURE WORKER'S COMPENSATION COVERAGE IS UNLAWFUL AND SHALL SUBJECT AN EMPLOYER TO CRIMINAL PENALTIES AND CIVIL FINES UP TO ONE HUNDRED THOUSAND DOLLARS (\$100,000) IN ADDITION TO THE COST OF COMPENSATION, DAMAGES AS PROVIDED FOR IN SECTION 3706 OF THE LABOR CODE, INTEREST AND ATTORNEY'S FEE.

THIS PERMIT SHALL EXPIRE BY LIMITATION IF WORK IS NOT COMMENCED WITHIN 180 DAYS.



DEPARTMENT OF
PLANNING AND DEVELOPMENT

CITY OF SACRAMENTO
CALIFORNIA

1231 I STREET
ROOM 200
SACRAMENTO, CA
95814-2998

Permit Services
916-264-7619
FAX 916-264-7096

Shirley Fong
327 Zephyr Ranch

95831 TILE ROOF WORKSHEET


This worksheet must be filled out whenever any type of tile roof is applied for.

If the answer to question #5 is yes, a written engineering report from a registered engineer must be provided with each application.

1. BRAND AND MODEL OF TILE Pioneer Lite weight
2. TILE WEIGHT PER SQUARE 7.30 lbs
3. WEIGHT OF ROOF SYSTEM PER SQUARE 1.80 lbs
4. TOTAL WEIGHT OF ROOF SYSTEM 9.10 lbs
5. DOES TOTAL WEIGHT OF ROOF SYSTEM EXCEED 750# PER SQUARE? YES NO
6. ROOF SLOPE 4/12

PLEASE PROVIDE A SEPARATE WORKSHEET FOR EACH APPLICATION INVOLVING A TILE ROOF

All attached engin. report



2

HEADER DETAIL

scale: 1 1/2" = 1'-0"

12

Reviewed by Matt P. 5/17/22

327 Zephyr Ranch

Fong-Taylor

Paul Zacher – Structural Engineers
4701 Lakeside Way
Fair Oaks, CA 95628

TEL: 916.961.3960
FAX: 916.961.3960

May 5, 1999

Zimmerman Roofing
3560 Ramona Avenue
Sacramento, CA 95826
TEL: 916.454.3667
FAX: 916.455.3784
TEL (Jeff): 916.392.1971
FAX (Jeff): 916.392.6853
FAX (Framer) : 916.383.5308



Attn: Mr. Jeff Tucker,

re: Job 99089: FONG / TAYLOR

Subject: Structural Investigation Report of the Roof for the Duplex located at 723 Zephyr Ranch and 7275 Bayview Way, Sacramento, CA 95831.

As requested by Mr. Jeff Tucker, this is a report to determine what needs should be addressed to correct any structural deficiencies of the roof. Paul Zacher visited the site on April 29, 1999 and May 5, 1999. The investigation was made to determine the existing condition of the structure. All information, data and analysis contained within this report is based on the 1994 Uniform Building Code.

The following is based on visual observations with no subsurface investigation being made.

DESCRIPTION:

Type of Facility: Duplex.
Year Built: Estimated 1970's vintage.
Occupancy: Residential.
No. of Stories: One.
Dimensions: Approximately 3000 square feet with a first story plate height of 8 feet.

CONSTRUCTION:

Roof:

The roof covering will consist of Pioneer Light Weight Concrete Tile over 1/2" solid sheathing. The living and garage areas are framed with wood pre-engineered trusses spaced at 24" on center.

Fong-Taylor

Paul Zacher – Structural Engineers
4701 Lakeside Way
Fair Oaks, CA 95628

TEL: 916.961.3960
FAX: 916.961.3960

CONCLUSIONS:

Roof:

The living area has sufficient structural capacity for the applied live and dead loads. The garage lacks sufficient structural capacity for the applied live and dead loads.

RECOMMENDATIONS:

If any of the following recommendations do not correspond to actual field conditions, the engineer of record shall be notified for further investigation and evaluation before continuing work.

Garage:

- 1 Scab a 2x12 DF#2 x 16'-0" long beam to the existing 4x12 garage header and nail together with 16d's @ 2' oc staggered. See details 1 and 2.


It shall be noted that small hairline cracking may occur at exterior stucco and interior gypboard finished walls which are load bearing or distributing roof strut loads. These cracks are a natural occurrence as the existing structure re-distributes the new roof weight. They are cosmetic in nature and are not an indication of a structural hazard or failure.

It shall be noted that some deflection of the rafters may be evident after installation of the tile. The existing roof framing has deflected but this may not be readily evident due to the uneven nature of the existing roofing material. Concrete tile is a very consistent and uniform product and when installed in an even plane, even small deflections can become apparent. This is only a cosmetic issue and not a structural concern.

The inspection consisted of visual observation only, made solely to determine the structural capacity of the existing roof. Analysis does not determine any effects on the overall structure under lateral forces or effects on the foundation unless specifically noted in the calculations and in this document. No warranties, expressed or implied, are made or intended in conjunction with this report. The inspection was made only to the portions that were accessible. The specific items noted were those that were observable and there may be defects which are not observable, or are hidden by architectural and structural materials.

If you have any questions on the above, do not hesitate to call.

Sincerely,



Paul Zacher, P.E., S.E.
File

DESIGN LOADING:

| | | |
|-------------------------|------|-------|
| Roof Pitch | 4 | in 12 |
| Pitch Adjustment Factor | 1.05 | |

LOCATION: TOP CHORD

| <u>MATERIAL</u> | <u>WEIGHT</u> | |
|-----------------------|---------------|-----|
| Pioneer Light Weight | 7.00 | psf |
| Roofing felt | 0.30 | psf |
| 1/2" OSB/ plywood | 1.50 | psf |
| 1x4 skip sht'g | 1.09 | psf |
| 2x4 truss @ 24" oc | <u>1.28</u> | psf |
| Load | 11.2 | psf |
| Roof Pitch Adjustment | <u>0.60</u> | psf |
| Total Load | 11.8 | psf |

LOCATION: BOTTOM CHORD

| <u>MATERIAL</u> | <u>WEIGHT</u> | |
|--------------------|---------------|-----|
| Batt/blown insul | 0.50 | psf |
| 2x4 truss @ 24" oc | 0.64 | psf |
| 1/2" Gypboard | <u>2.50</u> | psf |
| Load | 3.6 | psf |

Timber Beam & Joist

Description BEAMS

Timber Member Information

| | | |
|-----------------------|-----|---------------------|
| | | 4x12 + 2x12 |
| Timber Section | | 6x12 |
| Beam Width | in | 5.000 |
| Beam Depth | in | 11.250 |
| Le: Unbraced Length | ft | 2.00 |
| Timber Grade | | Douglas Fir - Larch |
| Fb - Basic Allow | psi | 875.0 |
| Fv - Basic Allow | psi | 95.0 |
| Elastic Modulus | ksi | 1,600.0 |
| Load Duration Factor | | 1.250 |
| Member Type | | Sawn |
| Repetitive Status | | No |

Center Span Data

| | | |
|-----------|------|--------|
| Span | ft | 15.25 |
| Dead Load | #/ft | 161.00 |
| Live Load | #/ft | 168.00 |

Results Ratio = 0.9973


| | | |
|---------------|------|-------------------|
| Mmax @ Center | in-k | 114.77 |
| @ X = | ft | 7.62 |
| fb Actual | psi | 1,088.2 |
| Fb Allowable | psi | 1,091.1 |
| | | Bending OK |
| fv Actual | psi | 58.9 |
| Fv Allowable | psi | 118.8 |
| | | Shear OK |

Reactions

| | | | |
|-------------|------------|-----|----------|
| @ Left End | DL | lbs | 1,227.62 |
| | LL | lbs | 1,281.00 |
| | Max. DL+LL | lbs | 2,508.62 |
| @ Right End | DL | lbs | 1,227.62 |
| | LL | lbs | 1,281.00 |
| | Max. DL+LL | lbs | 2,508.62 |

Deflections

| | | |
|-------------------|----|--------|
| Center DL Defl | in | -0.206 |
| L/Defl Ratio | | 886.6 |
| Center LL Defl | in | -0.215 |
| L/Defl Ratio | | 849.7 |
| Center Total Defl | in | -0.422 |
| Location | ft | 7.625 |
| L/Defl Ratio | | 433.9 |



VisualAnalysis 3.50.c Report

05/05/99 14:21:00

Project:

File: C:\Program Files\IES\VA35\Untitled.vap

Company: PK Associates Engineers

Engineer: Paul Zacher

Default Units: Feet, Pounds, Degrees, °Fahrenheit, Seconds.

Nodes

| Node | X ft | Y ft | Fix DX | Fix DY | Fix RZ |
|------|---------|---------|-----------|-----------|-----------|
| N1 | 0.00 | 0.00 | Yes | Yes | No |
| N2 | 8.25 | 0.00 | No | No | " |
| N3 | 16.50 | 0.00 | " | Yes | " |
| N4 | 16.50 | 3.25 | " | No | " |
| N5 | 18.00 | 3.00 | " | " | " |
| N6 | 24.00 | 2.00 | " | " | " |
| N7 | 30.00 | 1.00 | " | " | " |
| N8 | 36.00 | 0.00 | " | Yes | " |
| N9 | 8.25 | 2.75 | " | No | " |
| N10 | 16.50 | 5.50 | " | " | " |
| N11 | 18.00 | 6.00 | " | " | " |
| N12 | 24.00 | 4.00 | " | " | " |
| N13 | 30.00 | 2.00 | " | " | " |

Member Elements

| Member | Section | Material | Length ft | Weight lbs | Theta deg |
|--------|---------|----------|--------------|---------------|--------------|
| M1 | SS2x4 | Wood | 8.25 | 12.17 | 0.00 |
| M2 | " | " | 8.25 | 12.17 | 0.00 |
| M3 | " | " | 3.25 | 4.79 | 0.00 |
| M4 | " | " | 1.52 | 2.24 | 0.00 |
| M5 | " | " | 6.08 | 8.97 | 0.00 |
| M6 | " | " | 6.08 | 8.97 | 0.00 |
| M7 | " | " | 6.08 | 8.97 | 0.00 |
| M8 | " | " | 8.70 | 12.83 | 0.00 |
| M9 | " | " | 8.70 | 12.83 | 0.00 |
| M10 | " | " | 1.58 | 2.33 | 0.00 |
| M11 | " | " | 6.32 | 9.33 | 0.00 |
| M12 | " | " | 6.32 | 9.33 | 0.00 |
| M13 | " | " | 6.32 | 9.33 | 0.00 |
| M14 | " | " | 2.75 | 4.06 | 0.00 |
| M15 | " | " | 8.70 | 12.83 | 0.00 |
| M16 | " | " | 2.25 | 3.32 | 0.00 |
| M17 | " | " | 3.00 | 4.43 | 0.00 |
| M18 | " | " | 2.92 | 4.30 | 0.00 |
| M19 | " | " | 6.08 | 8.97 | 0.00 |
| M20 | " | " | 2.00 | 2.95 | 0.00 |
| M21 | " | " | 6.00 | 8.85 | 0.00 |
| M22 | " | " | 1.00 | 1.48 | 0.00 |

Section Properties

| Category | Section | Ax in ² | Iz in ⁴ | Sy+ in ³ | Sy- in ³ |
|----------|---------|-----------------------|-----------------------|------------------------|------------------------|
| Wood Sha | SS2x4 | 5.25 | 5.36 | 3.06 | 3.06 |

Material Properties

| Material | Strength ksi | Elasticity ksi | Poisson | Density lb/ft ³ | Therm. /F |
|----------|-----------------|-------------------|---------|-------------------------------|--------------|
| Wood | -NA- | 1700.00 | 0.36 | 40.47 | 0.00 |

VisualAnalysis 3.50.c Report

05/05/94 11:21:05

Project:

File: C:\Program Files\IES\VA35\Untitled.vap

Company: PK Associates Engineers

Engineer: Paul Zacher

Default Units: Feet, Pounds, Degrees, °Fahrenheit, Seconds.

Load Cases

| Load Case | Strength Service Results | | |
|---------------------|--------------------------|----|---------|
| (1)Service Case 1 | No | No | None |
| (2)Service Case 2 | " | " | " |
| (3)Equation Case 1 | " | " | 1st Ord |

Service Load Cases

| Load Case | Load Source | Self Weight | Loads |
|----------------|-------------|-------------|-------|
| Service Case 1 | Dead loads | None | |
| Service Case 2 | Roof Live 1 | " | |

Load Combination Summary

Equation Case: Equation Case 1

Combination: +1D+1L+1Lr+1R+1W+1S+1E+1H+1F+1TS+1T+1TC+1I+1U+1LE

Contributing Cases & Source

Service Case 1 (Dead loads)

Service Case 2 (Roof Live loads)

Equation Case Combinations

| Load Case | Cases Equation | |
|-----------------|----------------|------|
| Equation Case 1 | 0.00 | 0.00 |

Member Uniform Loads

| Load Case | Member | Direction | Offset ft | End Off ft | Magnitude |
|----------------|--------|-----------|--------------|---------------|------------|
| Service Case 1 | M1 | DY proj. | 0.00 | 8.25 | -0.01 K/ft |
| " | M2 | " | 0.00 | 8.25 | -0.01 K/ft |
| " | M4 | " | 0.00 | 1.52 | -0.01 K/ft |
| " | M5 | " | 0.00 | 6.08 | -0.01 K/ft |
| " | M6 | " | 0.00 | 6.08 | -0.01 K/ft |
| " | M7 | " | 0.00 | 6.08 | -0.01 K/ft |
| " | M8 | " | 0.00 | 8.70 | -0.02 K/ft |
| " | M9 | " | 0.00 | 8.70 | -0.02 K/ft |
| " | M10 | " | 0.00 | 1.58 | -0.02 K/ft |
| " | M11 | " | 0.00 | 6.32 | -0.02 K/ft |
| " | M12 | " | 0.00 | 6.32 | -0.02 K/ft |
| " | M13 | " | 0.00 | 6.32 | -0.02 K/ft |
| Service Case 2 | M8 | " | 0.00 | 8.70 | -0.03 K/ft |
| " | M9 | " | 0.00 | 8.70 | -0.03 K/ft |
| " | M10 | " | 0.00 | 1.58 | -0.03 K/ft |
| " | M11 | " | 0.00 | 6.32 | -0.03 K/ft |
| " | M12 | " | 0.00 | 6.32 | -0.03 K/ft |
| " | M13 | " | 0.00 | 6.32 | -0.03 K/ft |

VisualAnalysis 3.50.c Report

05/05/99 14:33:13

Project:

File: C:\Program Files\IES\VA35\Untitled.vap

Company: PK Associates Engineers

Engineer: Paul Zacher

Default Units: Feet, Pounds, Degrees, °Fahrenheit, Seconds.

Load Cases

| Load Case | Strength Service Results | | |
|---------------------|--------------------------|----|---------|
| (1)Service Case 1 | No | No | None |
| (2)Service Case 2 | " | " | " |
| (3)Equation Case 1 | " | " | 1st Ord |

Member Extreme Results

| Member | Fx(lc) K | Fy(lc) K | Mz(lc) K-ft | fc max(lc) ksi | fc min(lc) ksi | Dx(lc) in | Dy(lc) in |
|--------|------------------|------------------|------------------|-------------------|-------------------|------------------|------------------|
| M1 | 0.82(3) | -0.04(3) | -0.05(3) | 0.16(3) | -0.04(3) | 0.00(3) | -0.08(3) |
| " | 0.82(3) | 0.03(3) | 0.04(3) | 0.36(3) | 0.16(3) | 0.01(3) | -0.00(3) |
| M2 | 0.82(3) | -0.03(3) | -0.05(3) | 0.16(3) | -0.04(3) | 0.01(3) | -0.08(3) |
| " | 0.82(3) | 0.04(3) | 0.04(3) | 0.36(3) | 0.16(3) | 0.02(3) | -0.00(3) |
| M3 | -0.89(3) | -0.06(3) | -0.18(3) | -0.17(3) | -0.89(3) | -0.00(3) | -0.02(3) |
| " | -0.89(3) | -0.06(3) | -0.00(3) | -0.55(3) | -0.17(3) | -0.00(3) | 0.07(3) |
| M4 | -0.22(3) | -0.02(3) | -0.02(3) | -0.04(3) | -0.11(3) | -0.06(3) | -0.06(3) |
| " | -0.22(3) | -0.01(3) | 0.00(3) | 0.02(3) | -0.04(3) | -0.06(3) | -0.01(3) |
| M5 | 1.36(3) | -0.02(3) | -0.02(3) | 0.26(3) | 0.16(3) | -0.06(3) | -0.24(3) |
| " | 1.37(3) | 0.02(3) | 0.01(3) | 0.35(3) | 0.26(3) | -0.05(3) | -0.06(3) |
| M6 | 2.44(3) | -0.01(3) | -0.02(3) | 0.48(3) | 0.25(3) | -0.05(3) | -0.35(3) |
| " | 2.45(3) | 0.03(3) | 0.05(3) | 0.68(3) | 0.45(3) | -0.03(3) | -0.24(3) |
| M7 | 2.44(3) | -0.02(3) | 0.05(3) | 0.65(3) | 0.09(3) | -0.03(3) | -0.34(3) |
| " | 2.45(3) | 0.03(3) | 0.10(3) | 0.84(3) | 0.28(3) | -0.01(3) | -0.00(3) |
| M8 | -0.93(3) | -0.26(3) | -0.38(3) | -0.18(3) | -1.64(3) | -0.01(3) | -0.40(3) |
| " | -0.78(3) | 0.17(3) | 0.30(3) | 1.34(3) | -0.16(3) | -0.00(3) | -0.00(3) |
| M9 | -0.02(3) | -0.21(3) | -0.38(3) | 0.05(3) | -1.49(3) | -0.01(3) | -0.11(3) |
| " | 0.13(3) | 0.22(3) | 0.12(3) | 1.49(3) | -0.04(3) | -0.01(3) | -0.00(3) |
| M10 | -0.15(3) | 0.06(3) | -0.15(3) | -0.02(3) | -0.62(3) | -0.01(3) | -0.05(3) |
| " | -0.12(3) | 0.14(3) | -0.00(3) | 0.56(3) | -0.02(3) | -0.01(3) | -0.00(3) |
| M11 | -0.16(3) | -0.19(3) | -0.21(3) | -0.01(3) | -0.86(3) | 0.02(3) | -0.24(3) |
| " | -0.06(3) | 0.12(3) | 0.16(3) | 0.80(3) | -0.01(3) | 0.02(3) | -0.04(3) |
| M12 | -1.47(3) | -0.14(3) | -0.21(3) | -0.24(3) | -1.09(3) | 0.01(3) | -0.36(3) |
| " | -1.36(3) | 0.18(3) | 0.10(3) | 0.57(3) | -0.29(3) | 0.02(3) | -0.23(3) |
| M13 | -2.59(3) | -0.16(3) | -0.09(3) | -0.47(3) | -1.14(3) | -0.01(3) | -0.34(3) |
| " | -2.48(3) | 0.16(3) | 0.17(3) | 0.18(3) | -0.48(3) | 0.01(3) | -0.00(3) |
| M14 | 0.07(3) | 0.00(3) | 0.00(3) | 0.01(3) | 0.01(3) | 0.06(3) | 0.01(3) |
| " | 0.07(3) | 0.00(3) | 0.00(3) | 0.01(3) | 0.01(3) | 0.06(3) | 0.01(3) |
| M15 | -0.93(3) | 0.00(3) | 0.00(3) | -0.18(3) | -0.18(3) | 0.02(3) | -0.05(3) |
| " | -0.93(3) | 0.00(3) | 0.00(3) | -0.18(3) | -0.18(3) | 0.03(3) | 0.01(3) |
| M16 | -0.93(3) | 0.16(3) | -0.18(3) | -0.15(3) | -0.90(3) | -0.01(3) | 0.01(3) |
| " | -0.93(3) | 0.16(3) | 0.17(3) | 0.54(3) | -0.20(3) | -0.00(3) | 0.07(3) |
| M17 | -0.01(3) | -0.00(3) | -0.00(3) | -0.00(3) | -0.00(3) | 0.05(3) | -0.07(3) |
| " | -0.01(3) | -0.00(3) | 0.00(3) | -0.00(3) | -0.00(3) | 0.05(3) | 0.01(3) |
| M18 | 0.60(3) | -0.00(3) | -0.00(3) | 0.11(3) | 0.11(3) | -0.00(3) | 0.01(3) |
| " | 0.60(3) | -0.00(3) | 0.00(3) | 0.11(3) | 0.11(3) | -0.00(3) | 0.09(3) |
| M19 | -1.27(3) | -0.00(3) | -0.00(3) | -0.24(3) | -0.24(3) | -0.09(3) | -0.22(3) |
| " | -1.27(3) | -0.00(3) | 0.00(3) | -0.24(3) | -0.24(3) | -0.08(3) | -0.04(3) |
| M20 | 0.24(3) | -0.00(3) | -0.00(3) | 0.04(3) | 0.04(3) | 0.23(3) | -0.09(3) |
| " | 0.24(3) | -0.00(3) | 0.00(3) | 0.04(3) | 0.04(3) | 0.23(3) | -0.05(3) |
| M21 | -1.06(3) | -0.00(3) | -0.00(3) | -0.20(3) | -0.20(3) | -0.10(3) | -0.33(3) |
| " | -1.06(3) | -0.00(3) | 0.00(3) | -0.20(3) | -0.20(3) | -0.09(3) | -0.23(3) |
| M22 | 0.04(3) | 0.00(3) | 0.00(3) | 0.01(3) | 0.01(3) | 0.33(3) | -0.10(3) |
| " | 0.04(3) | 0.00(3) | 0.00(3) | 0.01(3) | 0.01(3) | 0.33(3) | -0.09(3) |

BENDING & COMP: TRUSS 1; MEMBER 13

Buckling Factor, CT is
 negelected due to small contribution

Grading:

2x or 4x Doug-fir larch: No. 2

Assumptions:

Lateral support at points of bearing
 SPS or gypboard attached to compression face
 Maximum center-center spacing = 24"

| | |
|-------------------------|-----------------------|
| Width, b | 1.5 inches |
| Depth, d | 3.5 inches |
| Length | 6.32 feet |
| Max Axial Comp, C | 2590 lbs |
| Max Reaction, R | 160 lbs |
| Max Moment, M | 90 ft-lbs |
| Max LL Deflection | 0.19 inches |
| Max TL Deflection | 0.34 inches |
| LL Defl Criteria = L/ | 240 |
| TL Defl Criteria = L/ | 180 |
| Duration factor, Cd | 1.25 |
| Repetitive Factor, Cr | 1.15 |
| fc = | 493 psi |
| Fce= | 1597 psi |
| Fc*= | 1094 psi |
| F'c= | 879 psi |
| fb= | 29 psi |
| F'b= | 1258 psi |
| Shear D/C ratio | 0.38 < 1.0, Member OK |
| Interaction equation: | |
| (fc/F'c) ² + | |
| fb/ (F'b(1-fc/Fce)) = | 0.35 < 1.0, Member OK |
| Live Load defl ratio | 0.60 < 1.0, Member OK |
| Total Load defl ratio | 0.81 < 1.0, Member OK |

① ROOF PLAN - TAYLOR WING
N.T.S.

